



INDO-GERMAN ENERGY FORUM

Flexible Thermal Power Plants: A Case Study

**Report No. 1: Flexibility Assessment for
the NTPC plants Dadri and Simhadri**
September 27, 2017





Document Control

Client:	GIZ / IGEF Task Force Flexibility
Project No:	15.9040.5-003.00
Report Title:	Flexibility Assessment for the NTPC Plants Dadri and Simhadri
Report No:	1 IGEF Flexibility
Authors	Dr. Claudia Weise (VGB), Mr. O.P. Maken (EEC), Dr. Christoph Guder (STEAG), Dr. Daniel Lehmann(STEAG), Mr. Manfred Schesack (STEAG)
Date of Issue:	September 27, 2017

Action	Responsible (Name, Function)	Signature	Date
Released by the Lead Author	Dr. Claudia Weise, Project Manager		
Approved by the Project Director	Dr. Oliver Then, Head of Power Plant and Environmental Technologies		





TABLE OF CONTENTS

List of Abbreviations5

List of Figures.....7

List of Tables9

1 Project Organization10

2 Executive Summary11

3 Project Charter18

4 Introduction20

4.1 Energy Transition in India and in Germany20

4.2 Coal-Fired Power Plants in India and in Germany22

5 Basics of the Case Study26

5.1 Flexible Operation – Terminology.....26

5.2 Approach for the Flexibility Assessment.....27

6 Status Quo of the Reference Power Plants31

6.1 General Information about the Reference Plants.....31

6.2 Status Quo of Dadri Power Plant – 210 MW_{el}.....33

6.3 Status Quo of Simhadri Power Plant – 500 MW_{el}41

7 Flexibility Examination for the Reference Plants52

7.1 Definitions52

7.2 Document List.....52

7.3 Dadri – Document Analysis54

7.3.1 Main Findings and Recommendations54

7.3.2 Minimum Load.....59

7.3.3 Start-up69

7.3.4 Ramp Rates80

7.3.5 Test program.....80

7.4 Simhadri (Stage 1 and 2) – Document Analysis81

7.4.1 Main Findings and Recommendations81

7.4.2 Minimum Load.....86

7.4.3 Start-up97

7.4.4	Ramp Rates	108
7.4.5	Test program.....	108
8	Assessment of the Flexibility Measures.....	110
8.1	Document List.....	110
8.2	Effect of Cycling Operation on Power Plants	110
8.2.1	Equipment Forced Outage Rate	110
8.2.2	Heat Rate.....	112
8.2.3	Cost Impact.....	113
8.2.4	Mitigation Measures	114
8.3	Assessing the Flexibility Measures.....	115
8.3.1	Assessment of the Dadri Measures	116
8.3.2	Assessment of the Simhadri Measures	117
8.3.3	Operating Procedures	118
8.3.4	Conclusions and Way Forward.....	119
Appendix A: List of reviewed documents provided by NTPC		122
Appendix B: VGB standard “Feed Water, Boiler Water and Steam Quality for Power Plants / Industrial Plants”		125
Appendix C: VGB standard “Preservation of Power Plants”		129
Appendix D: VGB standard “Preservation of Steam Turbo-Generator Sets”		134