

# MPL's journey towards Flexibilization-"Minimum Power Limit REDEFINED"

Date: 22<sup>nd</sup> November-2022

Presentation By:

**Team MPL** 



# Maithon Power Limited – A Brief Introduction



Vision: Empower a billion lives through sustainable, affordable and innovative energy solutions.



# **FACTS AND FIGURES**


First successful venture of **Public Private Partnership (PPP) model**, a joint venture of Tata Power and DVC.


**Capacity**: 1050 MW (525 MW X 2) Greenfield Project.

**Beneficiaries**: DVC, WBSEDCL, TPDDL, KSEBL

COD Unit-1 : 01.09.2011 COD Unit-2 : 24.07.2012


**Location:** Maithon, Jharkhand







Indian thermal power sector is undergoing a radical transition with the advent of highly intermittent and low-cost renewable power generation, affecting a fundamental change in the business model of fossil fuel generation. As of now around 78% of India's power generation is met by thermal generators inspite of the target as set by the Government of India to increase the renewable generation by three folds (172 GW by 2022). This would require coal-based stations to bring down the load even below their Technical Minimum Limit, reduce the start-up time and progressively advance towards high ramp rates. The low merit order stations would also be required to operate in a two-shift basis mode or move to reserve shutdown.




### TATA POWER

# Flexible Operation – Present Scenario for MPL in FY22



Final Schedule



### TATA POWER

# Flexible Operation-Thought Process




### CEA ventured

- Under the Indo German Energy Forum (IGEF) flexibility roadmap, a task force was set up in India.
- The task force is undertaking studies to identify flexibilization measures and carry out a costbenefit analysis to determine their scale-up potential.
- Based on the concept & importance of its strata, Unit-2 of MPL was selected by CEA-Ministry of Power, to conduct the flexibility test in Eastern Region.
- It is the second plant after NTPC Dadri to demonstrate the test in collaboration with IGEF.




## Why MPL invested?

- Averting reserve shutdown.
- Benchmark in operational excellence
- Positive impact on performance parameters
- Increase in revenue owing to higher power sales in near future.
- Low count of reserve shutdowns will lower Cost on Customer - 25 lakhs/start up.






Pre-Work and Preparedness for MTL Operation



With all such probable thoughts, numerous brainstorming sessions were conducted to make the process more robust and fool-proof. Test procedure was shared by Siemens and same was prepared as an SOP where all apprehensions were taken into consideration.



# Unfavourable Pre-Test Conditions and Mitigation Plan

2

3

4

5

1



Minimum Load Test was conducted in a relatively controlled conditions as has been mentioned.

Following were the apprehensions that were possible in all the tests that were conducted:

- 1. SCC could not be predicted. It varied from 0.58 to 0.65 kg/kwh. Coal flow variations were obvious.
- 2. Availability of adjacent mills can be an issue (breakdown).
- 3. Low ambient temp would increase the duty of SCAPH, if FGET could not be maintained above dew point temp, it would lead to cold end corrosion of APH baskets.
- 4. LTSH, Divisional, Reheater metal temp excursions.


Good quality coal has been fired (SCC was maintained at 0.60-0.62 kg/kWh) during the Minimum load test as well as Ramp test.

3 adjacent mills were in operation (B-C-D). Prior to the test, maintenance job of all 3 mills were completed and was ensured to run without any issue.

AGC and RGMO was kept intentionally OFF to prevent any load variations. RRAS and SCED were also stopped during the test periods

Steam coil air preheater (SCAPH) was charged at low load. Additional auxiliary steam supplied from adjacent unit

Coal flow distribution and velocity profile for all the 4 coal pipes of Mill-2D were tried to equalize for better combustion and flame stability.





# START OF IGEF TRIALS

**Observations:** 



On 20<sup>th</sup> July, Coal Damper Test was carried out in Mill-2D at 525 MW with a specific coal consumption (SCC) of 0.696 kg/kWh. Feeder loading of Mill-2D was kept in manual at a demand of 84% and its average coal flow was 58 TPH.

On 21<sup>st</sup> July, Coal Damper Test was carried out in Mill-2D at 290 MW with a specific coal consumption (SCC) of 0.631 kg/kWh. Feeder loading of Mill-2D was kept in manual and its average coal flow was 45 TPH.

- Variable orifice adjustment to equalize fuel in each corner.
- Low coal flow through D-3 (shortest pipe).
- Coal pipe temp were uniform in nature.
- Isokinetic sampling was done to rule out pipe choking.
- Longest pipe D-1 was kept at 100%.
- Coal flow of Mill-2D was reduced to 25 TPH, flame conditions at corner-1 and 3 deteriorated (at 290 MW).

Coal Pipe Corner	Damper Position (%)	Coal Flow (TPH)	Coal Pipe Velocity (m/sec)	Coal Flow Distribution (%)
D-1	100	18.8	28.3	30.8
D-2	60	20.6	17	35.7
D-3	100	5.5	27	11.6
D-4	73	8.5	29.6	21.4

### Final Condition of Mill-2D:

ked. O <sub>x</sub> , O <sub>2</sub>	Coal Pipe Corner	Damper Position (%)	
	D-1	100	
	D-2	60	
	D-3	65	
	D-4	73	

- Coal pipe-1,2 and 4 were OK as per Siemens and IGEF. Pipe-3 is suspected of being chok
- Changes in PA Flow by 5 TPH did not influence Corner-3. Changes with respect to  $NO_x$ ,  $O_2$  were not appreciable.
- Low mill outlet temp (70°C) due to wet coal.
- Issue may persist with the coal flow sensors.
- GCV of coal improved and mill outlet temp improved to 90°C.
- Damper position of D-3 was kept at 65% and preparations for 40% MTL started.

Minimum Load Test- 40% in Turbine Follow Mode (TFM)




On 22<sup>nd</sup> July, Minimum Load Test (40%) to 210 MW was carried out in Turbine Follow Mode with a specific coal consumption (SCC) of 0.63 kg/kWh.

### **Pre-test conditions:**

- Load
- Coal Flow
- MS Pressure
- Mill Combination preferred
- Burner Tilt
- SADC
- MS/HRH temp
- O<sub>2</sub> SP

- : 290 MW (55% load)
- : 182 TPH (SCC=0.63)
- : Manual at 140 kg/cm2
- : B, C, D, E (44 TPH,46 TPH,44 TPH and 42 TPH of coal feeding)
- : Manual control
- : Auto control at 75-90 mmWC.
- : Auto control
- : Auto control SP 4.9%.




<ol> <li>SCAPH was taken in service at 12:20 hrs</li> <li>RCV of TDBFP-2A was opened at 290 MW and further load drop to 275 MW.</li> </ol>	<ul> <li>Increase in SA temp from 35°C/35°C to 66°C/86°C.</li> <li>FGET at APH outlet increased to 129.6°C/127.7°C</li> <li>Fluctuation in drum level was in the range of +120 to -218 mmWC which was manually controlled.</li> </ul>
<ol> <li>BT was reduced to 50% from 55%.</li> <li>Load was reduced to 275 MW in CMC at 12:50 hrs and further reduction to 255 MW. MS press was 123 kg/sq.cm.</li> </ol>	<ul> <li>LTSH metal temp crossed the alarm limits (460°C).</li> <li>At 255 MW, TDBFP-2A was taken out of service. MCV and ACV of TDBFP-2B opened to 100% to cater the feedwater flow due to low extraction steam press.</li> </ul>
1. Faceday 25 area days and see days	
<ol> <li>Feeder-2E speed was reduced to minimum.</li> <li>Switch over to Turbine Follow mode at 240 MW. MS press SP was 110 kg/sq.cm where actual press was 109 kg/sq.cm.</li> </ol>	<ul> <li>At 13:55 hrs, Mill-2E was taken out of service.</li> <li>Load drop from 240 MW to 210 MW at 14:08 hrs. Feeder speed of B, C and D were reduced by 5% manually to reach 210 MW.</li> </ul>
1. Load=210 MW, MS press=107 kg/sq.cm was kept for 1 hour for stabilization	•Post stabilization load was increased to 230 MW in press control.Mill-2E was taken in service at 250 MW and TDBFP-2A at 270 MW. Unit load was further increased to 290 MW. CMC was taken in service and SCAPH was isolated.




Minimum Load Test- 40% (TFM)










r mate and connactitur j

#### MPL Minimum Load Test- 40% in CMC MAITHON POWER On 23rd July- Load SP: 290 MW concumption (SCC) of 0.61 ried out in CMC Load SP: 235 MW MS Pr SP: 130 ksc 10:30 TDBFP 2B taken o/s 13:00 kg/kWh. It 180 MW loa 🖬 TDBFP2A ACV : 100% open Drum level fluctuation 225 TDBFP A R/C valv TDBFP2A MCV: 68% open Furnace to WB DP: mm opened 11:00 Flame intensity improves 35 MMWC 13:30 SCAPH Charged Pre-test con Pre-test co M(550/100d) Load • Burner Tilt control . 270 FDF 2A was stopped • Cr • SAPC IC. Load SP: 275 MW Load reduced 11:00 13:30 • M MS Pr SP: 120 ksc • FD Fan-2B ampere :79 A sequentially : Unit ramp rate : 11:30 • 🕻 • 225 MW-210 MW-200 3 MW/min 14:00 MW IDF 2A was stopped Load reduced : CM 2E feed rate : 195 MW - 190 MW 14:00 11:30 ID Fan-2B ampere variation 20 tph AB/BC Fireball flickering Min Load SP: from 930 to 1040 A Load SP: 260 MW 12:00 Load raised to 200 MW 179 MW 14:30 MS Pr: 115 ksc Min Load achieved: 188.6 MW Load raised : 230 MW -Poor Flame condition Load raised to 290 12:00 14:30 250 MW Fireball of AB & BC unstable MW LTSH metal temp reached Unit ramp rate : 5 ~210 TPH SA Flow deviation IDF 2A & FDF 2A re-12:30 limit value of 460C mw/min started 15:00 in LHS and RHS WB TDBFP 2B taken i/s Load reduced to 250 MW MS Pr SP : 108 12:30 15:00 Load raised : 290 MW ksc MS Pr SP: 120 ksc 13:00 Unit Load Rate : 15:30 2 MW/min

Private and Confidential





## Minimum Load Test- Snapshots








On 26<sup>th</sup> and 27<sup>th</sup> July, Load Ramp test (0.5%, 1% and 1.5%) was carried out in CMC with a specific coal consumption (SCC) of 0.61 kg/kWh. It was also in the schedule to check for the feasibility of 180 MW load.

MPL

Pre-test conditions:		
• Load	: 525 MW	
Coal Flow	: 296 TPH (considering SCC=0.56)	
MS Pressure	: Auto control at 172.9 kg/cm <sup>2</sup>	
Mill Combination preferred	: B, C, D, E, F, G All feeders in Auto.	
Burner Tilt	: Auto control	
• SADC	: Auto control at 75-90 mmWC.	
MS/HRH temp	: Auto control	
• O <sub>2</sub> SP	: Auto control SP 3.56%.	
RGMO & AGC was kept OFF at 11:23 hrs	after communicating to the concerned authority.	
Superheater spray	: 30 TPH ( LHS/RHS=0/30 TPH)	
Reheater spray	: 11 TPH ( LHS/RHS=5/6 TPH)	
Superheater temp	: 539ºC at 11:33 hrs	
Reheater temp	: 535ºC at 11:33 hrs	
Reheater MTM temp	: 592ºC max at 11:38 hrs ( tag no- 260,258)	
UOFA and LOFA	: Auto control	





# Load Ramp Tests (290 MW to 210 MW)

Trial 1: No equipment status change

status change Trial 2: Mill 2E stopped

Trial 1: Mill 2E stoppedTrial 2: TDBFP-2B stopped

Trial 1: TDBFP 2A stoppedTrial 2: No change

Trial 1: Turbine Follow Mode
 Trial 2: CMC

290 MW -260 MW Ramp : 0.5% ( 2.5 MW/min)

260 MW -240 MW Ramp : 0.5% ( 2.5 MW/min)

240 MW -225 MW Ramp : 0.5% ( 2.5 MW/min)

> 225 MW -210 MW Ramp : 0.25% ( 1.25 MW/min)

265 MW -290 MW Ramp : 1% ( 5.25 MW/min)

250 MW -265 MW Ramp : 1% ( 5.25 MW/min)

210 MW -250 MW Ramp : 1% ( 5.25 MW/min) Trial 1: TDBFP 2A taken in service
 Trial 2:

 Trial 1: Mill 2E started
 Trial 2: TDBFP 2B taken in service

 Trial 1: No equipment status change
 Trial 2: Mill 2E started

### Key Challenges faced during Load Ramp Tests :

- •Drum level fluctuation while taking TDBFP out of service at 250 MW. Drum level controlled manually through ACV, MCV following level setpoint.
- HRH steam temperature maintaining < 520°C.
- LTSH and Divisional metal temp were going above alarm values during ramp up from lower loads.
- Dependency on Unit-1 for PRDS (Steam for SCAPH and TDBFP ACV).

### Key observations of IGEF/Siemens:

- •Flame Stability have been the major influencing factor for Minimum Load operation
- Drum level, metal temp excursions have been the major factor during load ramps

# ACCOLADES

# Becomes India's First Thermal Station to achieve stable 36% loading of Machine

IGEF @IGEFSO · Jul 23

Kudos to the excellent operator team from @TataPower for successful flexibility tests with 36% minimum load achieved. The Indian and German experts from Tata Power MPL, @VGBPowerTech and @Siemens\_Energy perform these tests supported by @MinOfPower @BMWi Bund @IGEFSO.



IGEF @IGEFSO · Jul 23

36% minimum load achieved at @TataPower @damodarvalleyco JV Maithon Thermal Power Station in #Jharkhand. New milestone for #power sector in #India! @MinOfPower @CEA\_India @PosocoIndia witnessing 188 MW low load operation from control room at site!



IGEF Twitter handle

To reinforce TATA POWER commitment to all the stakeholders, Unit 2 of MPL division successfully demonstrated minimum load test at 40 % & 36%. It was witnessed & appreciated by CEA,POSOCO,ERPC & IGEF . MPL is the second plant in India after NTPC Dadri to achieve 40% & first in eastern region

Private and Confidential | 25

**Replace feedwater recirculation valves with modulating type valves**, as opening of the valves causes big disturbances.

**Upgrade or implement new controls for turbinedriven boiler feedwater pumps** when fed by auxiliary steam from another unit, as the controls are not working properly. Currently increased trip risk and a lot of operator attention required.

Upgrade of drum level control for operation at minimum load. Implementation of automatic sequences for start-up and shut down of Mill, BFP, SCAPH etc.

Conduct a study of **thermal and mechanical feasibility** of part load operation with **different coal qualities**. **Chemistry Assessment**  Optionally an **online performance calculation**, which calculates key performance indicators and will help operators in maintaining the efficiency high.

Thermal/mechanical upgrade of exhaust flue gas part / air part for increase of flue gas temperature level for Part load operation as well as for better controllability of flue gas temperature


**Combustion investigation**, consisting of slagging/fouling potential, milling system, burner system and impact of fuel compositions if required. **Boiler tuning at site** (optional-Simulations for combustion optimization (optional), consisting of Firing optimization, Slagging and fouling, Part load efficiency improvement and Emission calculation).




### Bottlenecks for Flexibilization



MPL





### **Conclusion:**

- Any unit can be flexed; however, all units need not. The flexing needs is to be decided based on the grid support required from the unit.
- Moderate amount of flexibilization can be achieved with modification in operational practices.
- Higher level of flexibilization can be achieved with retrofits and the decision should be taken on case-to-case basis as in some cases the retrofit cost may be prohibitive.
- The providers of flexibility must be motivated by incentivization.

# Questions, If Any ?

**Disclaimer:** The contents of this presentation are private & confidential. Please do not duplicate, circulate or distribute without prior permission.



# **Thank You!**

Website: <u>www.tatapower.com</u>

Email Id: <a>soumyadip.baral@tatapower.com</a>

**Contact:** (+91) 9204857090